



**NOTES:**

1. CONCRETE: 5,000 PSI, TYPE 1L CEMENT
2. DESIGNED FOR TRAFFIC HS-20
3. DESIGNED FOR 4 ft. EARTH FILL ABOVE BOX
4. ASSUMED WATER TABLE DEPTH: 4 ft.
5. SEPARATE TOP AVAILABLE IF BASE ONLY NEEDED
6. RACKING & ARMS INSTALLED BY CONTRACTOR

APPROXIMATE WEIGHTS:  
(PARTS SHOWN: 6FT TALL)  
HR TOP 6FT: 8.30 TONS  
BASE 6FT: 8.70 TONS



**ELECTRICAL VAULT**

5'x8' BOX

**2.25**