



HW 60" RCP - 75" HOLE

NOTES:

1. CONCRETE: 4,000 PSI, TYPE I/II CEMENT
2. GRADE 60 REINFORCEMENT ASTM A615
3. ALL #5 BAR @ 8" O.C. (WALL, WINGS, APRON & FOOTER)
4. APPROXIMATED WEIGHT: 7.45 TON.



NC - HEADWALLS

60" HEADWALL

1.1