


 POUR-IN-PLACE
 PRECAST UNIT

		HERMITAGE, TN LENOIR CITY, TN FRANKLIN, TN CHATANOOGA, TN	
PH# 1-800-737-0707		DWG# SRS-531	
DATE: 09/12/08		SHEET# 1 OF 1	

PRECAST INLET / TYPE E (E-3 & E-4)

SCALE: NTS

- GENERAL NOTES:**
1. DOWELS SHALL BE #4 BARS, 12" LONG AT 9" C-C SPACING & INSTALLED BY PRECASTER USING "CONCRESSIVE 1090" TYPE II CLASS C EPOXY.
 2. MEDIAN DRAIN & PAVEMENT EDGE DRAIN OPENINGS - WILL BE 7" DIAMETER OPENING FOR 6" PIPING.
 3. REINFORCEMENT STEEL = 60 K.S.I. - SIZE, SPACING, & LOCATION WILL MEET AL-DOT STANDARD DETAIL (1-621-E3) INDEX NO.637
 4. MIN. CONCRETE 28 DAY STRENGTH - 5,000 P.S.I.
 5. 2" VERTICAL SLOT IN UPHILL SIDE OF INLET BOX, FROM SUBGRADE TO BOTTOM OF GRATE SEAT, FOR CONTINUOUS DRAINAGE OF THE MEDIAN.